HASSAN DIVISION.

The 17th December 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan division, up to 10th January 1898 for restoring Heragu Thenginkere, Register No. 1109, Hassan taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Heragu Thenginkere, Register No. 1109, Hassan taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Hassan division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for restoring the Heragu Thenginkere tank, Registered No. 1109, Hassan taluk.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork to cross bund	C. yds.	6 975
Do to bund	„	16,073
Turfing	S. yds.	15,636
Grade stones with *Vis-a-vis* stones..	Each.	46
B. M. stones	„	2
Registered number stones	„	2
Gauge stones	„	1
Repairing the sluice	Lump sum.	
Waste weir—		
Clearing draft	C. yds.	3,382
Rough stone work (new)	„	263

The 6th December 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan division, up to 10th January 1898, for restoring and extending the Changravalli anikat and channel. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring and extending the Changravalli anikat and channel;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Western Circle, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items.	Per.	Restoring the anikat.	Improvement of the channel.					Extension of the channel.					Grand Total.
			Excavation.	Constructing one bridge.	Re-arranging sluices.	Constructing eight weirs.	Total.	Excavation.	Constructing five weirs.	Constructing three bridges.	Constructing thirteen sluices.	Total.	
Blasting rock in foundation	C. yd.	118	...	...	...	...	...	...	...	...	...	...	118
Rubble masonry with burnt stone in surki mortar ...	C. ft.	24,202	...	...	...	...	...	...	...	...	...	...	24,202
Pointing with cement	Sqr.	51·25	...	...	...	...	...	...	...	...	...	...	51·25
Removing and re-fixing old slabs	Sft.	1,910	...	...	...	...	...	...	...	...	...	...	1,910
Burnt stone slabs dressed	C. ft.	1,147	...	...	...	...	...	...	...	...	...	...	1,147
Earth work widening & deepening channel	C. yd.	...	42,369	...	...	...	42,369	15,787	...	...	..	15,787	58,156
Removing boulders	C. yd.	...	4,011	...	...	...	4,011	9,207	...	...	..	9,207	13,218
Blasting rock	C. yd.	...	1,333	...	...	...	1,333	970	...	...	...	970	2,303
Earth work excavation	C. yd.	...	...	...	348	202	550	...	157	...	156	313	863
Burnt brick in mortar	C. ft.	...	...	184	...	...	184	...	...	552	...	552	736
Do do in surki mortar	C. ft.	...	...	...	2,552	1,120	3,672	...	794	...	1,144	1,938	5,610
Plastering in mortar	Sqr.	...	...	3·66	...	..	3·66	...	...	10·98	...	10·98	14·64
Do do in surki mortar	Sqr.	...	...	...	25·52	5·75	31·27	...	4·00	...	11·44	15·44	46·71
Burnt stone slabs dressed	S. ft.	...	...	154	522	398	1,074	...	146	4·10	234	790	1,864
Rough stone work new	C. yd.	...	...	...	348	214	562	..	179	...	156	335	897
Year stone	No.	...	...	...	...	8	8	...	3	...	...	3	11
Rough stone in surki mortar	C. ft.	...	...	773	...	...	773	...	...	2,229	...	2,229	3,002
Burnt stone pillars	C. ft.	...	...	22	...	...	22	...	...	64	...	64	86
Pointing in surki mortar	Sqr.	...	...	2·03	...	...	2·03	...	...	5·84	...	5·84	7·87
Guard stones	No.	...	...	4	...	...	4	...	...	12	...	12	16
Mile stones	No.	...	...	...	...	...	...	5	...	...	...	5	5
Index and furlong stones	No.	...	...	...	...	...	...	92	...	...	...	92	92
Bed grade stones	No.	...	...	...	...	...	...	97	...	...	...	97	97
Benching rock	C. ft.	...	...	...	...	...	...	..	96	...	...	96	96

The 30th November 1897.

Notice is hereby given that a sum of Rs. 30-3-0 stands due in the books of this office to one Sheik Berry for work done by him on Manjarabad-Subramanya road. If Sheik Berry or his legal representative or his authorized agent fail to prefer his claim to the said amount within one month from this date, the sum will be credited to Government.

A. S. NAGAVKAR, *Exec. Engineer.*

CHITALDRUG DIVISION.

The 4th December 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug division, up to 27th December 1897, for constructing a new tank near Gurusiddapur, Jagalur taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new tank near Gurusiddapur, Jagalur taluk" ; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Eastern Circle, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detail of work.	*Per.*	*Quantity.*	*Remarks.*
Bund—			
Earthwork	C. yd.	34,186	
Do	"	13,000*	
Digging seat of bund	"	4,166	
Clearing silt in the stream	"	1,232	
Clearing jungle	Lump sum.		
Turfing	S. yd.	8,364	
Grade stone	No.	15	
B. M. stone	"	2	
Top width stone	"	15	
Gauge stone	"	1	
Date stone	"	1	
Stone revetment	C. yd.	2,989	
Weir—			
Burnt brick in chunam	C. ft.	640	
Stone in chunam	"	581	
Apron	C. yd.	133	
Pointing	Lump sum.		
Excavating foundation and clearing draft	C. yd.	13,711	
Training bank	Lump sum.		
Channel—			
Excavation	Lump sum.		
Sluice—			
Excavation gravelly soil	C. yd.	28	
Brick in chunam	C. ft.	1,592	
Plastering with chunam	Sqr.	9·60	
Slabs	S. ft.	312	
Cut stone	Lump sum.		
Burnt stone in chunam	C. ft.	214	

*Earth from cody cutting.

The 14th December 1897.

It is hereby notified for information of the public that the travellers' bangalo at Davangere, once closed for repairs as per Notification in *Mysore Gazette*, dated 25th March 1897, is now re-opened for travellers.

K. PRAHLADA RAO, *Offg. Executive Engineer.*